Go Back to Agenda

CITY OF VINELAND

	DEPARTMENTAL REQUEST FOR PUBLIC BIDDING	RECEIVE
1.	NATURE OF REQUEST: 2013 City Road Paving Project	JUL 2 9 2013
2.	ENGINEER'S ESTIMATE: \$\frac{1}{671,936.41}\$ (If Engineer's Estimate has been prepared by anyone other than the person signing the form, please attach a copy of said Engineer's Estimate.)	BUSINESS ADMIN.
3.	AMOUNT BUDGETED FOR THIS REQUESTED ITEM: \$ 1,671,936.41	ž.
4.	BUDGETED ITEM: YES V NO (If no, is it an ordinance authorized material, service or supply?)	
	YES ✓ NO ORDINANCE NO.: 2012-40	-
	(B) Please identify the page number and line item appropriation sub-account: Budget Page No Account No. 021-0-00-000-2-5518	3201
5.	Check here if: Federal Funds UEZ Funds Davis Bacon Requirements	
	(If any of the above are checked, the project must be monitored by the department for compliance with prevailing wage rate policy and procedure	es.)
6.	Date to be Advertised: 8/13/2013	
7.	Date to be Received: 9/10/2013	

10. The following must be attached:

9. Special Conditions or Instructions:

Date to be Awarded: 9/24/2013

Summary of Project

Specifications

Plans (if applicable)

Bidders Mailing List (with emails of the vendor)

11. Specifications Prepared by:

Michael Russo, Assistant Engineer, Civil, Ext. 4092

AND EXTENSION NUMBER) (NAME, TITLE

12. Approved by:

SIGNATURE (DIRECTOR, DEPARTMENT HEAD, SUPERVISOR)

Send copies to: Purchasing Department **Business Administration**

2013 City Road Paving Project

(Various City Roads)

SCOPE OF WORK

This project will provide for the milling (various depth) and resurfacing (various depth) of selected city roadways. Broken / settled curbing will be replaced in-kind. This construction will also provide for handicap curb cuts. Provisions for bicyclists will be met utilizing bicycle-safe inlet grates. Drainage castings will be retrofitted with NJDOT approved eco-friendly curb header pieces to conform to Stormwater regulations. Removal and replacement, in kind, of existing Stormwater drainage facilities is a part of this project.

In the event that areas of base failure are identified, those sections shall be excavated and reconstructed accordingly. The following is the list of selected streets and their associated limits as well as a summary of the work involved:

Street	From	То	Comments
Elmwood	New Pear	Landis Avenue	3,900 SY milling and paving;
Avenue	Street	Larias Averice	associated concrete work
Evelyn	Landis Avenue	Chestnut Avenue	8,400 SY milling and paving;
Avenue			associated concrete work; Inlet
			removal/installation
Evergreen	Elmwood	Sutliff Avenue	1,300 SY milling and paving;
Avenue	Avenue		associated concrete work
New Pear	Valley Avenue	Sutliff Avenue	5,800 SY milling/pulverizing and
Street			paving; associated concrete work;
0001			inlet castings replacement
Northwood	New Pear Street	Landis Avenue	4,900 SY milling and paving;
Drive			associated concrete work
 Robert	Main Road	Evelyn Avenue	5,100 SY milling and paving;
Boulevard			associated concrete work; inlet
boolevala			castings replacement
	Knoll Drive	Dead End	5,000 SY milling and paving;
Southwood			associated concrete work; inlet and
Drive			pipe installation; inlet casting
			replacement
Sutliff Avenue	New Pear	Adams	1,900 SY milling and paving;
John Averice	Street	Avenue	associated concrete work
	Landis Avenue	Almond Street	4,900 SY milling and paving;
Vassar Place			associated concrete work; Inlet
Vassai i iace			removal/installation; Inlet castings
			replacement
Victory	New Pear	Landis Avenue	4,500 SY milling and paving;
Avenue	Street	Larias Averice	associated concrete work
Old Farm	Brewster Road	Dead End	2,200 SY milling and paving; Inlet
Drive		Dedd Liid	castings replacement