

CITY OF VINELAND

RESOLUTION NO. 2018-328

A RESOLUTION DECLARING THE EXISTENCE OF AN EMERGENCY REQUIRING DRAINAGE REPLACEMENT ON MILL ROAD BETWEEN LANDIS AVENUE AND PINE AVENUE AND AUTHORIZING THE PAYMENT OF BILLS FOR SAID SERVICES.

WHEREAS, the City Engineer has reported the existence of an emergency related to the failure of a 24" corrugated metal storm sewer on Mill Road, between Landis Avenue and Pine Avenue; and

WHEREAS, the Department of Public Work was unable to repair it due to the depth and extent of the damage; and

WHEREAS, since the attempted repair, a recent rain event caused significant flooding of the roadway, creating a hazard to the public health, safety and welfare; and

WHEREAS, due to this emergent situation, the City Engineer solicited quotations from three (3) contractors to complete the repairs; and

WHEREAS, authorization is requested to contract with lowest bidder, South State Inc., Bridgeton, NJ for the Mill Road Emergency Drainage Replacement, at a cost of \$218,300.00; and

WHEREAS, the Chief Financial Officer has certified the availability of funds for the above emergency;

NOW, THEREFORE, BE IT RESOLVED by the Council of the City of Vineland as follows:

1. That the City Engineer is hereby authorized and directed to contract with South State Inc., Bridgeton, NJ, for Mill Road Emergency Drainage Replacement (Mill Road between Landis Avenue and Pine Avenue), in the amount of \$218,300.00.

2. That the Purchasing Agent is hereby authorized and directed to issue purchase orders to with South State Inc., Bridgeton, NJ, for Mill Road Emergency Drainage Replacement (Mill Road between Landis Avenue and Pine Avenue), in the amount of \$218,300.00.

3. That payment is hereby authorized pursuant to said purchase orders in accordance with procedures for payment of bills and demands heretofore established by Ordinance number 1048.

Adopted:

---

President of Council

ATTEST:

---

City Clerk

## Reid Wanda

---

**From:** Maillet David J.  
**Sent:** Tuesday, August 14, 2018 10:05 AM  
**To:** Reid Wanda  
**Cc:** Myers Brian  
**Subject:** Mill Road Emergency Work  
**Attachments:** 18-014 Emergency Specs.pdf; Bid Form-Mill Road Emergency Drainage Replacement (08-09-18).pdf; Mill Rd Emergency Bid.pdf

Wanda,

Please take note that on Monday, August 6, 2018, the City Engineer, Brian Myers, declared the condition on Mill Road to be an emergency.

On that day, I solicited quotations from three contractors (Perna Finnigan, Garrison, and South State) to complete the repairs as described in the quotation request.

They were instructed to return their quotations by Thursday morning of that week (August 9, 2018). The quotes also were required to indicate the anticipated start date.

I received quotes from Perna Finnigan and South State. Garrison did not provide a quote. South State was the low bidder and had the earliest start date.

Attached to this email are the quotation package sent to the contractors as well as the quotes received.

Very truly yours,

David J. Maillet, P.E.  
Supervising Engineer  
Division of Engineering and Planning  
City of Vineland  
640 E. Wood Street  
PO Box 1508  
Vineland, NJ 08362-1508  
(856) 794-4000, extn. 4098  
[dmaillet@vinelandcity.org](mailto:dmaillet@vinelandcity.org)  
[www.vinelandcity.org](http://www.vinelandcity.org)

*\*The most dangerous thing you do everyday is simply exist above an asphalt surface\**



## Reid Wanda

---

**From:** Dickenson Bob  
**Sent:** Tuesday, August 7, 2018 8:27 AM  
**To:** Myers Brian; Mercado Miguel  
**Cc:** Guglielmi Mark; Maillet David J.; Reid Wanda  
**Subject:** RE: Declaration of Emergency

ok

**From:** Myers Brian  
**Sent:** Monday, August 6, 2018 2:54 PM  
**To:** Mercado Miguel <mmercado@vinelandcity.org>; Dickenson Bob <bdickenson@vinelandcity.org>  
**Cc:** Guglielmi Mark <mguglielmi@vinelandcity.org>; Maillet David J. <dmaillet@vinelandcity.org>  
**Subject:** Declaration of Emergency  
**Importance:** High

Mike/Bob –

There was a failure of a 24" corrugated metal storm sewer on Mill Road, between Landis Avenue and Pine Avenue. The Department of Public Works (DPW) attempted to repair the failure, but due to the depth and extent of the damage, was unsuccessful in repair. After the attempt, the intent was to go out to bid for repair of the system. However, as shown in the attached photograph taken on Friday, rain events cause significant flooding of the roadway and creates a hazard to the public health, safety, and welfare.

I recommend the issuance of a contract to repair the system utilizing emergency contract procedures.

Today, we will be sending out requests for quotations from at least three (3) contractors who we know to have the expertise to perform the work required.

Thanks,  
Brian

---

**Brian N. Myers PE CME**

City Engineer  
City of Vineland  
640 E. Wood Street  
Vineland, NJ 08362-1508

Direct Tel: (856) 794-4000 ext 4091  
Office Tel: (856) 794-4090  
Office Fax: (856) 405-4606  
Email: [bmyers@vinelandcity.org](mailto:bmyers@vinelandcity.org)



"We cannot solve problems with the same thinking we used when we created them" – Albert Einstein

**PROPOSAL**  
**MILL ROAD EMERGENCY DRAINAGE REPLACEMENT**  
(MILL ROAD BETWEEN LANDIS AVENUE AND PINE AVENUE)

The undersigned bidder declares he/she has read the NOTICE TO BIDDERS, INSTRUCTIONS TO BIDDERS and SPECIFICATIONS attached, that he/she has determined the conditions affecting the bid and agrees, if this proposal is accepted, and contract awarded, to complete the following:

<u>ITEM</u>	<u>DESCRIPTION</u>	<u>UNIT</u>	<u>QUANTITY</u>	<u>UNIT PRICE</u>	<u>TOTAL AMOUNT</u>
1	MAINTENANCE AND PROTECTION OF TRAFFIC	LS	1	<u>20,000.00</u>	<u>20,000.00</u>
2.1.2	CLEARING SITE	LS	1	<u>50,000.00</u>	<u>50,000.00</u>
4.1.2	REMOVAL OF PIPE, METAL/PLASTIC, ≤30" DIA., ≥7' DEPTH	LF	200	<u>20.00</u>	<u>4,000.00</u>
4.2.4	24" DIA. CORRUGATED POLYETHYLENE PIPE, SMOOTH WALL, ≥7' DEPTH	LF	200	<u>110.00</u>	<u>22,000.00</u>
4.3	CURED IN PLACE PIPING (CIPP)	LF	652	<u>135.00</u>	<u>88,020.00</u>
5.5.2	MILLING OF HMA, 4"-6" THICK	SY	270	<u>32.00</u>	<u>8,640.00</u>
6.2.1	DENSE GRADED AGGREGATE BASE COURSE (RECYCLED CONCRETE), 8" THICK	SY	270	<u>20.00</u>	<u>5,400.00</u>
7.1.3	HOT MIX ASPHALT 25M64 BASE COURSE, 4" THICK	TON	68	<u>180.00</u>	<u>12,240.00</u>
7.1.4	HOT MIX ASPHALT 9.5M64 SURFACE COURSE, 2" THICK	TON	34	<u>200.00</u>	<u>6,800.00</u>
13.1.1	TRAFFIC STRIPES, LONG LIFE, EPOXY RESIN, 4" WHITE	LF	240	<u>5.00</u>	<u>1,200.00</u>

TOTAL AMOUNT BID: 218,300.00

Company Name: South State Inc

Earliest Date Available to Start Work: 3 DAYS AFTER AWARD (BUSINESS)